




REVISIONS			
REV	DESCRIPTION	DATE	APPROVED



PORT-A-BRIDGE IS DESIGNED FOR 9" (MIN.) OF BEARING SURFACE ON EACH END OF BRIDGE.

**NOTE**  
CONTRACTORS ARE RESPONSIBLE FOR SUPPLYING BRIDGE WITH SUFFICIENT ABUTMENTS OR SUPPORT SYSTEMS TO ENSURE CORRECT POSITIONING AND BEARING OF BRIDGE.





### PORT-A-BRIDGE DISCLAIMER

GME IS PROVIDING A PORTABLE BRIDGE SYSTEM THAT IS A PRE-ENGINEERED TO CARRY A LOAD FOR THE FULL SPAN OF THE PORT-A-BRIDGE FROM CENTERLINE BEARING TO CENTERLINE BEARING. ALL BRIDGE UNITS ARE DESIGNED IN ACCORDANCE WITH AASHTO-US BRIDGE DESIGN CODES AND CAN SAFELY CARRY HS-25 LOADING.

CONTRACTORS SHALL BE RESPONSIBLE FOR THE FOLLOWING:

- HANDLING AND INSTALLATION OF THE PORT-A-BRIDGE.
- ABUTMENTS OR SUPPORT SYSTEMS INCLUDING ALL ANCHORS USED IN INSTALLATION OF PORT-A-BRIDGE.
- ALL JOBSITE CONDITIONS WHERE THE PORT-A-BRIDGE IS IN USE.

NO DRILLING, WELDING OR ALTERATIONS OF ANY KIND TO THE GME PORT-A-BRIDGE WITHOUT WRITTEN PERMISSION FROM GME.



### PORT-A-BRIDGE BASE PLATE FEATURES

BRIDGE BASE PLATE IS EQUIPPED WITH STOPS AT EACH END TO FACILITATE ANY LATERAL MOVEMENT THE BRIDGE MAY EXPERIENCE. NOTE BRIDGE TO BE INSTALLED ON BASE PLATE AND BEARING ON THE BASE PLATE STOP ON ONE SIDE OF THE BRIDGE TYPICAL AT EACH SUPPORT SYSTEM. THE STOPS ON THE OPPOSITE END OF BASE PLATE ALLOW FOR INSTALLATION VARIANCES, THEY ARE THEN SHIMMED AS REQUIRED TO ENSURE A TIGHT FIT AMONG SECOND SET OF STOPS AND BRIDGE SYSTEM.

REV.		SIZE	PARTS LIST			
A	B		ACAD FILE: C:\PRINTS 2007\PORT-A-BRIDGE\JOBSITE REFERENCE DATA\40ft Haunched Beam Port-A-Bridge			
UNLESS OTHERWISE SPECIFIED DIMENSIONS ARE IN INCHES			DO NOT SCALE DRAWING			
TOLERANCES			DRAWN	BPS	01/23/08	<b>GRISWOLD</b> <small>MACHINE AND ENGINEERING, INC.</small> <small>UNION CITY, MICHIGAN 49094</small>
DECIMALS ±.010 ANGULAR ±1°			CHECK	CHECKER	DATE	
.XXX ±.005 FRACTIONS ±1/16			ENG	ENGINEER	DATE	TITLE: 40' HAUNCHED BEAM PORT-A-BRIDGE
.XXXX ±.0005			PROD	PROD	DATE	DWG. NO. 40FT HAUNCHED PORT-A-BRIDGE
MATERIAL STEEL			QC	QC	DATE	SCALE: 1/1 DEPT: PORT-A-BRIDGE SHEET 1 OF 1
TREATMENT TREATMENT			MFG	MFG	DATE	
FINISH FINISH			TOOLING	TOOLING	DATE	